

# Pikes Peak REGIONAL Building Department

## ESCALATOR VIOLATIONS TABLE

<i>Violation</i>	<i>60 Day Notice w/ Follow Up</i>	<i>30 day Notice w/ Follow Up</i>	<i>Shutdown</i>
Acceptance Testing or Alteration Testing Failure			X
Category 1 Witness Testing Past Due (less than 30 days)		X	
Category 1 Witness Testing Past Due (more than 30 days)			X
Category 1 Witness Testing Failure of items listed on the test form (except for the items listed in this table that may warrant a follow-up instead of a shutdown)			X
Comb Plates not Meshing with Step Treadways			X
Comb Plates with one broken tooth not adjacent to another broken tooth	X		
Comb Plates with two or more adjacent teeth broken			X
Demarcation Lighting not working	X		
Fuses (installation of any oversized fuses in any elevator related equipment)			X
Handrail Drive Chain Components not examined / adjusted / repaired and logged in MCP every 6 months as required per PPRBD Policy			X
Maintenance Control Program missing or incomplete	X		
Safety Circuit Switches or Electrical Protective Devices Not Working			X
Safety Devices Purposely Disabled			X
Step to Skirt Clearance Excessive in the Transition/s			X
Step to Skirt Indexing Test Failure			X
Violations (other than those listed in this table)	X		
Violations (that present a life safety risk)			X