

Pikes Peak REGIONAL Building Department

ESCALATOR VIOLATIONS TABLE

<i>Violation</i>	<i>60 Day TCO</i>	<i>30 day TCO</i>	<i>Red Tag Notice</i>	<i>Shutdown</i>
Acceptance Testing or Alteration Testing Failure				X
Category 1 Witness Testing Past Due (less than 30 days)		X		
Category 1 Witness Testing Past Due (more than 30 days)				X
Category 1 Witness Testing Failure of items listed on the test form (except for the items listed in this table that may warrant a TCO instead of a Shutdown)				X
Comb Plates not Meshing with Step Treadways				X
Comb Plates with one broken tooth not adjacent to another broken tooth	X			
Comb Plates with two or more adjacent teeth broken				X
Demarcation Lighting not working	X			
Fuses (installation of any oversized fuses in any elevator related equipment)				X
Handrail Drive Chain Components not examined / adjusted / repaired and logged in MCP every 6 months as required per PPRBD Policy				X
Maintenance Control Program missing or incomplete	X			
Repairs / Replacements / Alterations performed without permits (where permits are required)				X
Safety Circuit Switches or Electrical Protective Devices Not Working				X
Safety Devices Purposely Disabled				X
Step to Skirt Clearance Excessive in the Transition/s				X
Step to Skirt Indexing Test Failure				X
Violations (other than those listed in this table)	X			
Violations (that present an imminent life safety risk)				X