

Pikes Peak REGIONAL Building Department

ELEVATOR VIOLATIONS TABLE

<i>Violation</i>	<i>60 Day Notice w/ Follow Up</i>	<i>30 day Notice w/ Follow Up</i>	<i>Red Tag Notice</i>	<i>Shutdown</i>
Acceptance Testing or Alteration Testing Failure				X
Category 1 Testing Failure of items listed on the PPRBD Test Form (except for the items listed in this table that may warrant a follow-up instead of a shutdown. This applies to Conveyance Mechanic Testing, not Witness Testing)				X
Category 1 Testing Past Due (between 31 and 60 days, excluding: Emergency or Standby Power Testing)		X		
Category 1 Testing Past Due (less than 30 days, excluding: Emergency or Standby Power Testing)	X			
Category 1 Testing Past Due (more than 60 days, excluding: Emergency or Standby Power Testing)			X	On Notice Date
Door Bottom Gib missing / broken or loose (where 2 are installed per panel) (1st notice)	X			
Door Bottom Gib missing / broken or loose (where 2 are installed per panel) (multiple notices)			X	On Notice Date
Door Bottom Gib missing / broken or loose (where a single gib is installed per panel)				X
Door Bottom Retainer / Fire Tab missing where required (1st notice)	X			
Door Bottom Retainer / Fire Tab missing where required (multiple notices)			X	On Notice Date
Door Closing Force Exceeds 30 lbf (1st notice)	X			
Door Closing Force Exceeds 30 lbf (multiple notices)			X	On Notice Date
Door Restrictors inoperable or out of adjustment where required (1st notice)	X			
Door Restrictors inoperable or out of adjustment where required (multiple notices)			X	On Notice Date

Violation	60 Day Notice w/ Follow Up	30 day Notice w/ Follow Up	Red Tag Notice	Shutdown
Emergency Lights and / or Alarm Bell Not Working	X			
Emergency Phone Not Working (1st notice)	X			
Emergency Phone Not Working (multiple notices)			X	On Notice Date
Fire Fighters Emergency Operation Components missing or inoperable (1st notice)	X			
Fire Fighters Emergency Operation Components missing or inoperable (multiple notices)			X	On Notice Date
Fuses (installation of any oversized fuses in any elevator related equipment)				X
Maintenance Control Program missing or incomplete	X			
Ropes larger than 8MM undersized, rouged, broken wires, etc.. (1st notice)	X			
Ropes larger than 8MM undersized, rouged, broken wires, etc.. (multiple notices)			X	On Notice Date
Ropes less than 8MM rouged, undersized, broken wires, etc..				X
Safety Circuit Switches or Electrical Protective Devices Not Working				X
Safety Devices Purposely Disabled				X
Suspension Belt Monitoring or Residual Strength Detection equipment not working		X		
Violations (other than those listed in this table)	X			
Violations (that present a life safety risk)				X
Witness Testing Failure (except for the items listed in this table that may warrant a follow-up instead of a shutdown)				X
Witness Testing Failure of Emergency or Standby Power Testing	X			
Witness Testing Past Due		X		